



Status Report on the Drift Chambers

Brian S. Henderson
Massachusetts Institute of Technology
OLYMPUS Collaboration Meeting
June 27, 2011



Outline

- Installation and alignment
 - Pre-installation tests
 - Installation of chambers into detector frame
- Recent and in-progress work
 - Testing of all wires
 - Electronics installation
 - Wire repairs
 - HV conditioning
- Work to be completed before roll-in
 - Completion of repairs and conditioning
 - Testing, cosmic ray runs

Pre-Installation Work

- ❑ Chambers moved to DORIS hall in late April
- ❑ Leak checking
 - Douglas Hasell
 - $2 \cdot 10^{-2}$ mL/s leak detector sensitivity
 - No noticeable leaks
- ❑ Signal testing
 - Alexander Winnebeck
 - Section of chamber brought successfully to operating voltage
 - Signals from cosemics were observed



Installation



June 27, 2011

OLYMPUS Collaboration Meeting

4

Installation

- Chambers installed into the main detector frame in early May by Jim Kelsey (MIT Bates)
- Alignment and Survey
 - Karen Dow (MIT Bates) and Martin Noak (DESY)
 - Chambers fit well between coils
 - Nominal position achieved to approximately ± 1 mm
 - Final survey position will be used in MC and RECON
- Gas lines installed
- Chambers flushed and retested for leaks

Wire Testing and Repair



Thanks to Axel Schmidt for the photos

Wire Testing and Repair


- Graduate students arrived in mid/late May
 - Brian Henderson (MIT), Lauren Ice (ASU), Colton O'Connor (MIT), Becky Russell (MIT), Axel Schmidt (MIT)
- All ~10000 wires checked for continuity and crossings
 - Visual inspections for slack wires
- Necessary repairs made in situ
- Repairs are ongoing as new problems are identified

Electronics Installation


- HV cards tested at Bates last semester
 - 125% of nominal voltage
- High voltage and front-end cards installed for both chambers
 - Cards for outer layers installed using aluminum hinges
 - Works reasonably well, some air space left between cards
- All cabling (HV, LV, signal) is complete for both chambers




Electronics Installation





Electronics Installation



Electronics Installation



Cabling



HV Conditioning

- ☐ Voltage applied to all cells
- ☐ All but ~20 cells on each chamber held 1500 V on first attempt
- ☐ Problems
 - Slack wires
 - ☐ Often caused by loose pins
 - ☐ Easily repaired
 - Bad insulation on HV boards
 - ☐ Attempting repairs with corona dope
 - ☐ Spare cards available if needed

Current Status

- ☐ Beam right chamber
 - All wire related issues repaired
 - Only five problem cells remain
 - ☐ All HV card issues (problem persist when all connectors removed)
 - HV conditioning continues on all other cells
 - Should be able to see signals this week
- ☐ Beam left chamber
 - ~15 issues identified
 - Repairs in progress, likely finished this week
 - Most cells hold 2500 V

Upcoming Work

- ☐ Finish repairs, bring to nominal voltage
- ☐ Observe signals
- ☐ Test the mapping of sense wires to the readout
- ☐ Test with the DAQ chain
- ☐ Test in the magnetic field
- ☐ Cosmic ray runs

Things are looking good for roll-in...

