OLYMPUS Collaboration Meeting, DESY, June 27-28, 2011

GEM Luminosity Monitor

Michael Kohl

Hampton University, Hampton, VA 23668 Jefferson Laboratory, Newport News, VA 23606

















The OLYMPUS Detector



The OLYMPUS Experiment

- Electrons/positrons (100mA) in multi-GeV storage ring DORIS at DESY, Hamburg, Germany
- Unpolarized internal hydrogen target (buffer system) $3x10^{15}$ at/cm² @ 100 mA \rightarrow L = $2x10^{33}$ / (cm²s)
- Large acceptance detector for e-p in coincidence Previous BLAST detector from MIT-Bates
- Redundant monitoring of luminosity
 Pressure, temperature, flow, current measurements
 Small-angle elastic scattering at high epsilon / low Q²
 Symmetric Moller/Bhabha scattering
- Measure ratio of positron-proton to electron-proton unpolarized elastic scattering to 1% stat.+sys.

Luminosity Monitors: GEM + MWPC


 Forward elastic scattering of lepton at 12 degrees in coincidence with proton in main detector


- Two GEM + MWPC telescopes with interleaved elements operated independently
- Scintillator for triggering and timing
- High redundancy alignment, efficiency
 Two independent groups (Hampton, PNPI)



Prototypes:

GEM





Luminosity Monitors – Basic Properties

Proposed version included in OLYMPUS TDR Sept. 2009

E_0	Q^2	$p_{e'}$	ϵ	θ_p	p_p	Rate
[GeV]	$[(\mathrm{GeV/c})^2]$	$[\mathrm{GeV/c}]$			$[\mathrm{MeV/c}]$	$[h^{-1}]$
4.5	0.801	4.073	0.9736	58.7°	992	1846
2.0	0.167	1.911	0.9774	71.8°	418	49792

Table 4.1: Kinematics and count rates of the luminosity control measurement for beam energies of 2.0 and 4.5 GeV at $\theta_e = 12^{\circ}$. The assumed solid angle is 1.2 msr determined by the area of rearmost tracking plane farthest from the target.


- Two symmetric GEM telescopes at 12°
- Two-photon effect negligible at high-ε / low-Q²
- Sub-percent (relative) luminosity measurement per hour at 2.0 GeV, per day at 4.5 GeV
- 1.2 msr = $10 \times 10 \text{ cm}^2$ at $\sim 290 \text{ cm}$ distance (rearmost plane)
- Three GEM layers with ~0.1 mm resolution with ~50 cm gaps


Principle of GEM Detectors

• **GEM = Gas Electron Multiplier** introduced by F. Sauli in mid 90's, F. Sauli et al., NIMA 386 (1997) 531

Copper layer-sandwiched kapton foil with chemically etched micro-hole pattern

gas amplification in the hole





Providing GEM detectors for OLYMPUS

Collaboration HU-MIT-Rome

TechEtch/MIT to provide GEM foils
Assembly of detectors at MIT-LNS, MIT-Bates and Hampton Univ.
INFN Rome: Readout system developed for Hall A / SBS
Testing at HU and DESY

Funding

- Secured NSF Nuclear Physics basic research grant (PHY-0855473: \$405k for 3 years, active since Aug. 2009)
 1 postdoc; travel funds
 2 undergraduate stipends for summer 2010
- Secured \$216k within NSF MRI-R2 for luminosity monitors (PHY-0959521: \$216k, active since Feb. 2010)
 1 grad. stipend + travel for commissioning
- Subaward to MIT (\$77k) established within MRI grant for MIT-Bates engineering services and ordering of parts

The HU group at DESY (2011)



Thanks to NSF and DOE!

Tasks & Timeline for LuMo Construction




Table 2: Revised work plan for GEM luminosity monitor construction activities.

- Above original schedule from TDR (black) with June 2011 updates (red)
- Construction of GEM detectors started at MIT in summer 2010
- New research building at HU with lab space available since October 2010
- Completed assembly of GEMs at Hampton in March 2011 with partial testing
- Testing at DESY spring 2011 (DESY testbeam facility in May-June 2011)
- Final installation in OLYMPUS main detector in summer 2011

Realization of Detectors

- Begin of 2010: Construction project fully funded (NSF/MRI-R2)
- Established HU-MIT subaward for Bates engineering services
 - Drawings, direct ordering of parts, technical support for manufacturing
 - Mechanical parts designed, ordered (June 2010) and delivered by July 2010
 - Readout board designed, ordered (November 2010) and delivered by January 2011
- GEM and HV foils from Tech Etch, Inc., 10x10 cm²
 - Foils designed and ordered April 2010
 - 35/35 GEM foils delivered, 12/12 HV foils; 16/16 GEM foils for GEM2D by July 2010
- HU group visited MIT and Bates from June 7 August 8, 2010
 - Frame preparation and cleaning
 - Testing of GEM foils (100% inspected, 30% optically scanned; 100% HV tested)
 - Stretching and gluing of PV, HV, and GEM foils on G10 frames (35% complete)


The Group at MIT (Summer 2010)



Realization of Detectors (cont'd)

- Completed GEM assembly at HU from Sept 2010 March 2011
 - Preparation of new lab space
 - Gluing of foils on frames
 - HV tests repeated after gluing / leak current measurements all GEMs still good!
 - Voltage divider and cosmic ray test setup with GEM2D chamber
 - Gain measurements with sources and picoammeter before gluing
 - Cosmic ray setup with preamplified signal
 - Tested and fixed final readout boards before gluing
 - Glued nine (9) GEM elements by end of March ("S0 ... S8")
- JD visit INFN Rome in February with HU GEM & readout board
 - Establish FE card functionality, optimize for OLYMPUS GEM
 - Complete assembly and testing at HU by mid March 2011
- Shipped detectors + electronics to DESY in April 2011
 - Delivery of VME crate, CPU, HV modules to HU February March 2011
 - Preparation for testing at DESY testbeam facility in May June 2011
 - Assembly of telescopes, install in OLYMPUS in June July 2011


Schematic view of a triple GEM



GEM Readout Board

- Want compact 12.5x12.5 cm² total area, 10x10 cm² active area
- Straps to extend out on the sides with strips to fit into connectors on Rome APV readout cards: 4 straps/connectors per card = 128 channels;
- Pitch of 400 μm (2 cards each on 2 sides). Designed, ordered and delivered.

- Readout technology with strips and pads, on 2-sided foil, vias-connected on rear side
- Previous technique based on laser ablation discontinued




Final boards had on average ~5 shorts on each,
 all of which were identified and repaired

D.Hasell


Strips & Pads Readout (B. Buck)

400 µm pitch - Total view (schematically)




Voltage Dividers

voltage divider with fast trigger output




PCB layout: B. Abruzzio




Parts received at DESY end of May 9 VDs tested, cabled, still to be coated with Epoxy

Readout Electronics (INFN Rome)




- Frontend card (APV + VME) by INFN Rome (S. Frullani)
- First test of INFN GEMs w/ new APV readout at DESY in November 2010
- JD visiting Rome with OLYMPUS GEM in February 2011 / 4 APV cards+VME
- 23 APV cards received on June 16; 2x20m HDMI cables received on June 22 another 3 APV cards expected. New batch will be produced due to issues
- 2(+1) final VME FPGA boards expected for first or second week of July

CAD model of **GEM** on bracket




APV cards mounted on flexible plates

CAD model of **GEM** on bracket





APV cards mounted on flexible plates


Lumi Telescopes (Sept 2010)




Lumi GEMs w/ services and rails








Lumi arm with MWPCs mounted on June 10, 2011



Bolt is in the way and needs to be shortened!



Clearance for gas line routing



Along the 12-degree line from target

Installation Procedure

- Wire chambers: Installed and surveyed by May 27:
 - Assume that WC will not be moved any more (see discussion on TOF positions
 - WC location in agreement with CAD model
 - Mount lumi telescopes and survey relative to wire chambers
- Trial mounting of pre-assembled arm on 6/10, repeated on 6/24 in both sectors
 - Reproduce 12 degree line within 1-2mm using two GEM brackets w/ crosshairs
 - Verify clearances of upstream element
 - Mount MWPC such that they fit
 - Assess remaining space for additional detectors (calorimeter?)
- -> Issues/observations:
 - Bracket stability: more rigidity w/ new holes closer to the bend
 - Wire chamber mounting bolt conflicting with MWPC electronics (left sector)
 - Wire chamber gas line routing
 - First GEM could move further upstream by ~20 cm / add 4th GEM in January?
 - Downstream end: space for calorimeter (e.g. scintillator/lead sandwich) for elastic single-arm trigger
- Assembly on bench, survey of GEMs only; mount MWPC and survey;
 install telescopes in OLYMPUS and survey (GEM survey impossible after MWPC)



Assembly of first telescope in progress (6/27)

Installation Schedule

- Mon 6/28 Continue assembly of GEM telescopes, make cables, modify APV boards
- Tue 6/29 Silicon telescope at testbeam 22 will be re-commissioned
- Wed 6/29 Last day of testbeam: Test with 3-GEM telescope
- Thu 6/30 Clear testbeam 22 area, transfer to workspace in DORIS hall
- Sun 7/03 Remaining 2 MWPCs arrive, 2 days to prepare installation
- Tue 7/05 Finish assembling GEM-only telescopes on bench with cables, gas lines; remove cables for survey and installation
- Wed 7/06 Survey and installation of GEM+MWPC luminosity monitor telescopes
 - Survey GEM-only telescopes on bench/wall in DORIS hall relative to RK support
 - Mount MWPCs on telescopes in predefined positions
 - Survey GEM+MWPC telescopes on bench/wall
 - Mount telescopes into OLYMPUS
 - Survey telescopes relative to wire chamber and detector
- Thu 7/07 Cabling of GEM+MWPC telescopes
- Fri 7/08 Routing of cables and gas; patch panels